

Room Finish Schedule for RAPCONs			
Space	Floor	Walls	Ceiling
Admin-Chief Controller	Carpet	Paint or vinyl wall covering	Suspended Acoustical Ceiling Tile (SACT)
Admin-CATCT-CSE (Chief Air Traffic Control Training, Chief Standardization and Evaluation)	Carpet	Paint or vinyl wall covering (VWC)	SACT
Admin-CBI (Computer-based Instruction)	Carpet	Paint or VWC	SACT
Admin-Administrative Area	Carpet	Paint or VWC	SACT
Male Restroom	Ceramic Tile (CT)	CT	Gypsum board (GYP)
Locker	Carpet	Paint	GYP
Shower	CT ¹	CT ¹	GYP
Female Restroom	CT	CT	GYP
Locker	Carpet	Paint	GYP
Shower	CT ¹	CT ¹	GYP
Mechanical	Concrete (Conc)	Paint	Exposed (Exp)
Electrical	Conc	Paint	Exp
Telephone Room	Conc or Vinyl Tile Composition (VCT)	Paint	Exp
TERPS/DSS (Terminal Procedures/Data Systems Specialist)	Carpet	Paint	SACT or Exp
Operations/Instrument Flight Rules (IFR) Room	Raised floor w/ integrated carpet	Paint	Exp or SACT ²
Simulator Room	Raised floor w/ integrated carpet	Paint	Exp or SACT ²
Briefing/Conference Room	Carpet	VWC	SACT
Vestibule	Carpet	Paint or VWC	SACT
Equipment Room	Raised floor w/ linoleum	Paint	Exp or SACT ²
Storage Room	Conc	Paint	Exp
Maintenance Room	Conc	Paint	Exp or SACT ²
Break Room	Carpet or VCT	Paint or VWC	SACT
Corridors	Carpet	Paint or VWC	SACT
Janitor	Conc or VCT	Paint	GYP

¹ Can also use prefabricated shower stalls

² Specify a 9'-0" ceiling height minimum, if SACT used

Note: The following table is to be used as a tool to be filled out when developing the Project Definition Customer Concept Design (CCD) and to be utilized at the RAPCON design charrette.