

### 3.4 STORM WATER POLLUTION PREVENTION

The Contractor is authorized to perform land disturbing activities and exterior facility work under the scope of this project. The project does not require a Georgia National Pollutant Discharge Elimination Standard (NPDES) general permit for construction activity.

#### 3.4.1 References

- |    |                           |   |
|----|---------------------------|---|
| a) | GA Rule 391-3-03k         | Water Quality Standards   |
| b) | GA Rule 391-3-7           | Erosion and Sedimentation Control   |
| b) | Cobb County, Article VIII | Soil Erosion and Sedimentation Control  |
| b) | Erosion Control Manual    | Manual for Erosion and Sediment Control in Georgia (4th Edition 1996, or Current) |
| c) | Storm Water P2 Plan       | Dobbins ARB Storm Water Pollution Prevention Plan (June 2001 or Current)          |

#### 3.4.2 Submittals

##### 3.4.2.1: Project Specific Storm Water Pollution Prevention Plan

#### 3.4.3 Storm Water Pollution Prevention Plan

3.4.3.1 The Contractor shall submit a project specific Storm Water Pollution Prevention Plan (SWPPP)(Submittal 3.4.2.1) for government review and approval prior to the start of work. The Contractor is prohibited from beginning land disturbing activities until the SWPPP has been approved by the Contracting Officer.

3.4.3.2 A General Construction SWPPP for Dobbins ARB is available to be used as a template for the Contractor to develop the Project Specific SWPPP. The Contracting Office will provide the template plan to the Contractor at the preconstruction meeting. The template is available in both electronic and hard copies.

3.4.3.3 The Project Specific SWPPP shall include the following:

- a) Base Project Information (Project Name, Project Number, Contact Information, Project Engineer, Project Inspector);
- b) Contractor Information (Contractor Name, Contact Information, Supervisor Name, Supervisor Contact Info.);
- c) Project Disturbed Area (acres);
- d) Certification Statement Provided and Contractors Signature;
- e) Erosion & Sedimentation Control Plan (1/2 Scale Project Drawings). If the Project Drawings do not include Erosion and Sedimentation Control Plans, the Contractor is responsible for generating a plan in accordance with Cobb County and State of Georgia Requirements;
- f) Erosion and Sedimentation Control Maintenance Procedures;
- g) Best Management Practices for Storm Water Pollution Prevention;
- h) Inspection and Monitoring Program

#### 3.4.3 Storm Water Pollution Prevention Requirements

3.4.4.1 The Contractor shall comply with the government approved project specific storm water pollution prevention plan including all erosion control practices, best management practices, housekeeping, and storage

requirements included within.

3.4.4.2 No fuels, oils, acids, wastes, or other materials shall be permitted to enter these water resources directly or through storm drain inlets in accordance with Georgia Rule 391-3-03k Water Quality Standards.

3.4.4.3 **The Contractor is prohibited from pouring ANY material down a storm drain.** Exceptions to this requirement may be granted by the Contracting Officer after a written request if the requested discharge is allowable under Dobbins permitting requirements.

3.4.4.4 If the Contractor believes he/she has encountered federally protected floodplains or wetlands not specified in the contract during the execution of work, the Contractor shall stop work on the site immediately and notify the Contracting Officer.